

## SCHEDULE 4 to the GMP ADDENDUM

### *DeSoto Fire Training Tower*



### **Clarifications, Assumptions Exclusions and Allowances**

#### Clarifications

- Electrical Bid Package includes the following scope, as per the PreBid and subsequent site visit meetings:
  - Provide and install 2 – 2 ½” PVC conduits with 3 - #250 XHHW conductors in each conduit from transformer between pole barn and metal building (as noted at site meeting). The conduits will be installed in a ditch that will be trenched and covered up by others. These conduits and conductors are for secondary power which means its customers responsibility.
  - Provide and install a stand-alone 400-amp Single phase 120/240-volt underground service that will be placed at the NE corner of the pole barn. 400-amp single phase meter can, 400-amp single phase Nema 3R panelboard, and 400-amp ground system. This service will be installed on 2 – 6” x 6” x 8’ concrete post with Unistrut between them for mounting.
  - Provide and install 3 – single pole 20-amp breakers in 400-amp standalone panel for future power needs in the barn.
  - Provide and install 1 – 200-amp single phase breaker that will be installed in the standalone panel for future building feed.
  - Provide and install 1 – 2 ½” conduit and (4) #2 and (1) #6 THHN from standalone service to tower location. Conduit will be tied into the standalone panel at one end and tie into a 100-amp 120/208-volt 3 phase panel at the fire tower. Panel in tower TBD. Ditch will be trenched and covered up by others.
  - Provide and install standard lighting, egress lighting, exit lighting, and standard receptacles as needed in the tower. No layout was given for locations or quantities.
  - Provide and install 1” conduit with pull string to future propane location. Conduit will be tied into 400-amp panel and stubbed up at future propane location.
  - Provide equipment that will be needed to complete tasks listed above.

#### Assumptions

- It is assumed that a room in the Turner Center could be utilized for field office and meetings.

#### Exclusions

- Job/Office Trailer
- Fencing
- Sitework (other than Fire Line and Hydrant)
- Survey
- Permit Fees
- Fees associated with the power company not included.
- F/A, data, TVSS, anything associated with heat sensing equipment, and anything associated with pyrometer equipment not included.
- At the request of the Owner, there is no Allowance/Contingency included in the GMP

#### Allowances

- None

205 Century Blvd, Bartow, FL 33830-7705

(863) 533-7193 Fax (863) 533-3376

[www.semcoconstruction.com](http://www.semcoconstruction.com)

License CGC040492